



THE UNDERSIGNED IS (ARE) AUTHORIZED BY THE SCHOOL DISTRICT TO REVIEW AND ACCEPT THE DESIGN OF THE BUILDING SPACE(S) REPRESENTED IN THIS DRAWING. ACCEPTANCE INCLUDES SIZE, SHAPE, ROOM LAYOUT, AND CONTENTS, INCLUDING ITEMS NOT IN CONTRACT (N.I.C.). ACCEPTANCE INDICATES THAT THE UNDERSIGNED HAS REVIEWED THE INFORMATION WITH THE ARCHITECT AND IS AUTHORIZING THE ARCHITECT TO IMPLEMENT THE DESIGN IN THE FINAL CONSTRUCTION DOCUMENTS.

ACCEPTED AS PRESENTED - SIGN \_\_\_\_\_ DATE \_\_\_\_\_  
 PRINT \_\_\_\_\_  
 ACCEPTED AS PRESENTED - SIGN \_\_\_\_\_ DATE \_\_\_\_\_  
 PRINT \_\_\_\_\_  
 ACCEPTED W/COMMENTS - SIGN \_\_\_\_\_ DATE \_\_\_\_\_  
 PRINT \_\_\_\_\_  
 ACCEPTED W/COMMENTS - SIGN \_\_\_\_\_ DATE \_\_\_\_\_  
 PRINT \_\_\_\_\_

COMMENTS  
 1. \_\_\_\_\_  
 2. \_\_\_\_\_  
 3. \_\_\_\_\_

GENERAL NOTE IN REFERENCE TO I4.1 DRAWING  
 1. ELECTRICAL CONTRACTOR SHALL DISCONNECT ALL EXISTING EQUIPMENT AND RECONNECT EXISTING AND NEW EQUIPMENT AT FINAL LOCATION.  
 2. GENERAL CONTRACTOR SHALL INSTALL ALL NEW EQUIPMENT AND RELOCATE ALL EXISTING EQUIPMENT TO TEMPORARY AND/OR FINAL LOCATION PER DRAWINGS AND/OR OWNER.

GENERAL NOTE IN REFERENCE TO I4.1  
 1. ALL CASEWORK IN TECHNOLOGY EDUCATION SHALL RECEIVE LOCKS.

GRADES 9 - 12 MOUNTING HEIGHT SCHEDULE	
MARKER BOARD	3'-0" AFF TO BOTTOM EDGE
TACK BOARD	3'-0" AFF TO BOTTOM EDGE
BASE CABINETS	2'-10" AFF TO TOP OF COUNTER
WALL CABINETS	7'-0" AFF TO TOP OF CABINET
SMART TV - OWNER PROVIDED/OWNER INSTALLED	3'-0" AFF TO BOTTOM EDGE

GENERAL NOTES TO APPLY TO ALL I4 DRAWINGS

- MOUNTING HEIGHT SCHEDULE IS APPLICABLE TO MOST ROOMS. IN INSTANCE WHERE NOTE/DETAILS ON DRAWINGS DO NOT COINCIDE WITH THE SCHEDULE. THE DRAWINGS TAKE PRECEDENCE.
- ALL BASE CABINETS SHALL RECEIVE A CONTINUOUS 1-1/4" THICK LAMINATE COUNTERTOP WITH A 4" BACKSPLASH UNLESS NOTED OTHERWISE. THE DEPTH OF THE COUNTERTOP SHALL EXTEND 3/4" PAST THE DEPTH OF THE BASE CABINET.
- COUNTERTOPS THAT RETURN INTO A WALL(S) SHALL RECEIVE BACKSPLASH THAT WRAPS CORNER ALONG WALL(S).
- PROVIDE CHAMFERED EDGE CORNER FOR ALL COUNTERTOPS ADJACENT TO ALL TALL STORAGE UNITS.
- WHERE COLUMNS, WINDOWS OR OTHER BUILDING COMPONENTS CONFLICT WITH CASEWORK DIMENSIONAL REQUIREMENTS. FIELD VERIFY DIMENSIONS AND PROVIDE CUSTOM UNIT TO ALLOW PROPER FITTING.
- ALL EXPOSED ENDS OF CASEWORK SHALL RECEIVE FINISHES END PANELS.
- LAMINATE COLOR FOR INTERIOR OF OPEN CABINETS SHALL MATCH EXTERIOR LAMINATE COLOR.
- STAINLESS STEEL SINKS, FAUCETS, AND BUBBLERS SHALL BE PROVIDED AND INSTALLED BY PLUMBING CONTRACTOR.
- CASEWORK SPECIFIED AS 'LSI SCIENCE' SHALL RECEIVE EPOXY SINKS, COUNTERTOP WITH 4" BACKSPLASH UNLESS OTHERWISE NOTED. EPOXY SINKS, FAUCETS AND BUBBLERS SHALL BE PROVIDED AND INSTALLED BY CASEWORK CONTRACTOR. CONNECTIONS SHALL BE PROVIDED BY PLUMBING CONTRACTOR.
- ALL VISUAL DISPLAY AREAS (MARKER BOARDS AND/OR TACK BOARDS) 10'-0" W OR LONGER SHALL RECEIVE 2" MAP RAIL THAT SPANS FROM VERTICAL EDGE TO VERTICAL EDGE.
- PROVIDE WOOD BLOCKING IN METAL STUD WALLS, PER MANUFACTURER'S RECOMMENDATIONS, TO RECEIVE THE TELEVISION WALL BRACKET.
- IN ROOMS RECEIVING RESILIENT BASE, ADHERE TO ALL WALLS, BASE CABINET TOE KICKS, AND EXPOSED END PANELS. REFER TO SPECIFICATIONS FOR LOCATION OF 4" AND 6" BASE.
- SEE REFLECTED CEILING PLANS FOR LOCATION OF WINDOW TREATMENTS.
- TELEPHONE UNITS AND SYSTEMS ARE NOT IN CONTRACT.
- COORDINATE ALL LARGE SCALE PLANS WITH MECHANICAL, ELECTRICAL AND PLUMBING DRAWINGS.
- NIC = NOT IN CONTRACT
- WHEN DESCRIPTION AND MODEL NUMBER IN CASEWORK AND EQUIPMENT SCHEDULE CONFLICT, THE DESCRIPTION TAKES PRECEDENCE.
- OPP = OPPOSITE HAND.

REVISIONS

NO.	DATE	BY	DESCRIPTION OF CHANGES

**CRABTREE ROHRBAUGH & ASSOCIATES - ARCHITECTS**  
 401 EAST WINDING HILL ROAD  
 MECHANICSBURG PA 17055  
 717-458-0272 FAX 717-458-0047  
 250 WEST MAIN STREET, SUITE 200  
 CHARLOTTESVILLE VA 22902  
 434-975-7262 FAX 434-975-7263  
 www.cra-architects.com

**CR**  
 LARGE SCALE LAYOUTS  
 GROWLER, CLASSROOM, &  
 TECHNOLOGY EDUCATION LAB  
 PLOT SCALE:  
 1/4" = 1'-0"  
 FILENAME:  
 DATE: DECEMBER 27, 2018

RENOVATIONS TO  
**BIG SPRING HIGH SCHOOL**  
**BIG SPRING SCHOOL DISTRICT**  
 100 MOUNT ROCK ROAD, NEWVILLE PA 17241

**PROJECT**  
 3106.2  
**I4.1**